


GENERAL NOTES:



1. REFER TO THE 2017 CITY OF EDMONDS STORMWATER ADDENDUM FOR SETBACK AND INFEASIBILITY REQUIREMENTS.

NOTES:

1. A VEGETATED FLOW PATH MUST BE PROVIDED IN ACCORDANCE WITH THE 2017 CITY OF EDMONDS STORMWATER ADDENDUM REQUIREMENTS.
2. MATERIAL FOR ROCK PAD SHALL BE WASHED DRAIN ROCK CONFORMING TO WSDOT SPEC. 9-03.12(5), GRAVEL BACKFILL FOR DRYWELLS.
3. SLOT DRAINS OR ASPHALT BERMS MAY BE USED TO DIRECT RUNOFF TO ROCK PADS OR DISPERSION TRENCHES IN VARIOUS CONFIGURATIONS. LAYOUTS SHOWN ARE ONLY EXAMPLES.
4. CONVEYANCE PIPE SHALL BE 4-INCH (MIN) DIAMETER, PVC DRAIN PIPE PER WSDOT SPEC. 9-05.1(5), POSITIVE SLOPE.



PLAN - DRIVEWAY WITH DIAGONAL BERMS



PLAN - DRIVEWAY WITH SLOTTED DRAINS



CITY OF EDMONDS
PUBLIC WORKS
DEPARTMENT

TYPICAL CONCENTRATED FLOW DISPERSION

APPROVED BY: R. ENGLISH

REVISION DATE
DECEMBER 2017

STANDARD
DETAIL
SD-634